Mississippi Artificial Reef Habitat Early Restoration Phase I Early Restoration

PROJECT DESCRIPTION

The Mississippi Department of Environmental Quality (MDEQ) implemented the Mississippi Artificial Reef Habitat Phase I Early Restoration Project to help restore natural resources of the Gulf following the 2010 *Deepwater Horizon* oil spill (Spill). Valued at \$2.6 million, the Artificial Reef Habitat project enhanced existing nearshore reefs within Mississippi waters. The hard bottom provided valuable nearshore habitat and shelter sites for small crustaceans and mollusks, as well as juvenile shrimp, crab and oysters that live on the reef and in the sediment.

During the fall of 2012 and spring of 2013, barges equipped with a large crane and an attached clamshell bucket were used to hoist crushed, domestic limestone and place it on the existing reefs in coastal waters. A total of 28,530 cubic yards of the limestone cultch were deployed on 47 of the 67 artificial reef locations in Jackson, Harrison and Hancock counties.

Secondary productivity monitoring of this project is complete; data are available at https://www.gulfspillrestoration.noaa.gov/.

Funding for this project is the result of an April 21, 2011 negotiated commitment from BP to provide \$1 billion for early restoration Gulf wide. When negotiated, the agreement was the largest of its kind. Of the \$1 billion, Mississippi was allocated \$100 million. More information about this project and other restoration efforts can be reviewed at www.restore.ms.



Existing artificial reef areas (each approximately three acres in size) enhanced with clean, crushed limestone.





